


Vision of a small hydro research
project from the owner's point of
view

Initial situation
End 1999

TARGET
End 2002



SEARCH
LHT
→
project



Controlled manually
216kW double Francis 26m
Efficiency
Reliability: excellent

- Can bus based control with optical link with water intake
- 330kW 8 blades Kaplan 1000rpm 27m
- efficiency
- 100 000h maintenance free
- Final Budget: 700 000€




Time

- Researchers need time (for good)(Mhylab, EPFL INPG)
 - Flow modelisation (end 3003)
 - Laboratory tests (end 2003)
- Once research is over application starts
 - Lot of work, worries, problems for small companies
 - Turbine manufacturing: end 2004
 - Control system:
 - First operation (main functions february 2005)
 - Finished (2006)
- Conclusion
 - All partners need a lot of time
 - The owner must not be in a hurry (as usual owners)

Finance

- Initial budget: 480k€, UE funding 110k€ end 1999
- Only once researchers have finished precise budget is known (end 2003) +220k€ (building)
 - UE refused to contribute on those extra costs
 - ADEME accepted to contribute (thank's a lot)
- Insurance do not like prototype machines (but banks oblige to have comprehensive insurance)
- Once financial report issued for a period (6 months) payment by UE not before a year
- Contractual problems: for one manufacturer development cannot be contractualised
- Conclusion
 - To budget a cost for a demonstration site following a research, the usual 10% for miscellenious should be over quoted (over over)
 - Don't forget late payments from UE

EFFICIENCY of the TURBINE



Objective fully reached

Conclusion

- Significant progress can be obtained on small hydro if proper research is funded
- Demonstration site results confirm completely results found by researchers

RELIABILITY

- **After one year of operation**
 - **Turbine**
 - Water cooled bearing: OK
 - Clearance between blades and wheel mantle: OK
 - Capability for operation at very low power (10kW): OK
 - No cavitation
 - Weakness in wheel boss (insufficient fixing of levers axis): significant problem, repaired now
 - **Control Command (only minor items)**
 - Few bugs have been cured and to be cured
 - Industrial PC at water intake blocked (low temperature probably)
 - One restart of satellite internet connexion hub
 - **Global operability**
 - A bit more energy should have been put in commissioning
 - Operator need time to get familiar with the control system
- **Conclusion**
 - Initial objective for :
 - the turbine not reached yet, but reachable (we think)
 - The control system reached

Conclusions

- You have to be a special owner “to give” your site for demonstration for a research project:
 - Do it for pleasure, not money
 - Time should not be of importance for you
 - Give your confidence to research people
- It is hard for small manufacturer to get in a project like this one, they have to be thank for their efforts
- We are very pleased to have done it. Significant improvements have been proven
- Now, it is up to YOU, here, to apply all this work on your hydro sites :
 - For your Kaplan turbines
 - For your control systems

SEARCH LHT Partners

- Mhylab
- EPFL
- LEGI (INPG)
- Turbine manufacturer: THEE
- Control Command: SASSO
- Demonstration site in France SEER
- Demonstration site in Swizerland: Romande Energie